

Document No.:	ITP-10-003	Revision:	0
Title:	Inspection & Test Plan — Pumps and Instruments	Status:	DRAFT
Project:	Unit 10/20 Process Plant	Date:	2024-03-15

Inspection & Test Plan — Pumps and Instruments

1. Scope

This Inspection and Test Plan covers rotating equipment and instrumentation installed within Unit 10 process plant.

2. Pump Testing

All pumps 10-P-101A/B/C shall be hydrostatically tested at 1.5 times design pressure prior to installation. Performance curve testing is required for 10-P-101A and 10-P-101B in accordance with API 610.

Chemical dosing pump 10-P-103 shall be calibrated against the vendor data sheet.

3. Instrument Calibration

Instruments 10-FT-1001 to 1005 require calibration prior to loop check. Calibration certificates shall be submitted to the document controller within 5 days of completion.

Temperature transmitters 10-TT-1001 to 1003 shall be calibrated against a certified reference standard. Level transmitters 10-LT-1001, 10-LT-1002, and 10-LT-1003 shall be calibrated using a water column.

4. Pressure Safety Valves

Pressure safety valves 10-PSV-1001, 10-PSV-1002, 10-PSV-1003, and 10-PSV-1004A/B shall be bench-tested and certified by an approved PSV workshop prior to installation.

5. Strainers

Y-strainer 10-STR-101 and duplex strainer 10-STR-102 shall be flushed and inspected prior to commissioning.

End of Document